



SCHEDULE OF ELECTRICAL LIGHTING AND POWER SYMBOL				
N0.	SYMBOL	DESCRIPTION	MOUNTING HEIGHT	
1		6A 1GANG 1WAY SWITCH	1400MM A.F.F.L	
2	<u></u> 4F	1200MM,18W LED BARE BATTEN FLOURESCENT FITTING	CEILING	
3	<u> </u>	9W LED surface mounted day light down light	CEILING	
4	2	wall mounted examination lamp @ 1200mm a.f.f.l	1200MM A.F.F.L	
5	趎쑈	13A twin switched socket outlet 1400mm/300mm a.f.f.l.	1400MM/300MM A.F.F.L	
6	©	Nurse call		
7	NCP	Nurse call panel.		
8	SD	Smoke detector	CEILING	

NOTES

- 1.All electrical installation shall comply with the the requirement of IEE regulations.
- 2.Internal wiring shall be carried out in PVC Insulated single core cables as East African cables or approved equivalent
- 3. All electrical instructions shall come from PEE.
- 4. All conduits to be done before plaster.

COUNTY GOVERNMENT OF NAKURU



DDO IECT

PROPOSED CONSTRUCTION OF KIPTANGWANY MATERNITY AT ELEMENTAITA WARD

CLIEN.

DEPARTMENT OF HEALTH SERVICES

CLIENT SIG

ELECTRICAL DRAWING BS

DATE	2024	
SCALE	1:50	
DRAWN BY	B.B.N	
CHECKED BY	J.W.G	DRG NO.
Job No.		001